

15-065-20072-00-00

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
8-16-67  
AUG 16 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Dreiling Well No. 2

Location: CE/2-SW-SW Sec. 28 Twp. 9 Rge. (E)(W) 24

County Graham Total Depth 4100 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

203' --8 5/8" Surface pipe, cement circulated with 165 Sx. Dakota section from 1070' to 1230'.

Circulate hole with heavy mud. Pull DP. to 1250' and displace 90 Sx. cement thru. DP. Pull DP to 200' and displace 25 Sx. cement thru DP. Pull DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols  
Conservation Division Agent