

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1914
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gib Scheck of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Scheck guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Bieker Well No. 1

Location: SE-SW-SE Sec. 30 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4135' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Scheck was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 200 Sx.
4114'--4 1/2" Production casing cemented on bottom with 175 Sx. Top of perforations @ 3922'.

Push plug to 3400', sand back to 3350' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. G. Dickala
Conservation Division Agent