



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
11-26-73  
NOV 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Gib Scheck of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Scheck guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated.

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Bieker Well No. 2

Location: NW-SW-SE Sec. 30 Twp. 9 Rge. (E)(W)24

County: Graham Total Depth 4132 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Scheck was instructed to plug the well as follows:

238'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4127'--5 1/2" Production casing cemented on bottom with 125 Sx. Top of perforations @ 3963'.

Push plug to 3900', sand well back to 3850' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent