



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-8-74
MAR 8 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Delta Western Company & G. Reed,

Complete Address: 1223 Union National Building, Wichita, Kansas.

Lease Name: Critchfield Well No. 4

Location: CNW/4 Sec. 33 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4125 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

299'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent