

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21294-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 3-32S-19W  
660 feet from S Section Line, 990 feet from W Section Line  
Lease Name: BIRD N Well #: 1  
County: COMANCHE Total Vertical Depth: 6258 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.38	189		WITH 300 SX CMT
PROD	4.5	5420	3600	WITH 200 SX CMT
SURF	8.625	686		WITH 335 SX CMT

203.39

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2009 12:05 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DEON HOWARD Company: PICKRELL DRILLING Phone: (316) 262-8427

Proposed Plugging Method: PUMP 25 SX CMT & 100# HULLS. PLUG AT 1080' WITH 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 270' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/30/2009 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 50 SX CMT. TAGGED CMT AT 4650'. 1ST PLUG AT 1080' WITH 15 SX GEL, 100# HULLS, & 50 SX CMT. 2ND PLUG AT 720' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5240	5244		
5231	5234		
5200	5210		
5027	5031		

INVOICED  
DATE 2-12-09  
INV. NO. 200906119

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 05 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
FEB - 3 2009  
KCC DODGE CITY

*[Handwritten signature]*