

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20813-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 17-31S-18W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BURKHALL Well #: 2  
County: COMANCHE Total Vertical Depth: 5300 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5180	2885	WITH 150 SX CMT
RBP		5050		
SURF	8.625	638		WITH 300 SX CMT

172.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2009 1:22 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE Phone: (620) 770-0995

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2009 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT AT 4730'. 1ST PLUG AT 1050' WITH 15 SX GEL, 50 SX CMT, 100# HULLS. 2ND PLUG AT 660' WITH 50 SX CMT, 100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4997	5000		

INVOICED  
DATE 2-12-09  
INV. NO. 2009061198

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 03 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JAN 29 2009  
KCC DODGE CITY