

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21595-00-00  
Spot: SWSWSENV Sec/Twnshp/Rge: 2-28S-33W  
2501 feet from N Section Line, 1344 feet from W Section Line  
Lease Name: KOEHN Well #: 5-F2-28-33  
County: HASKELL Total Vertical Depth: 2950 feet

Operator License No.: 32309  
Op Name: PRESCO WESTERN LLC  
Address: 5665 FLATIRON PKWY  
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2951	0	WITH 300 SX CMT
SURF	8.625	896		WITH 400 SX CMT

95.88

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2009 12:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 20 SX CMT. PLUG AT 2000' WITH 15 SX CMT. PLUG AT 900-0' WITH 70 SX CMT. CHECK BACKSIDE WITH 10-15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/30/2009 2:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

GEL SPACER THEN PUMP 300# HULLS & 20 SX CMT AT 2725'. 1ST PLUG AT 2000' WITH 15 SX CMT. 2ND PLUG AT 900' WITH 79 SX CMT TO SURFACE. CHECK BACKSIDE. PRESSURED UP IMMEDIATELY.

Perfs:

Top	Bot	Thru	Comments
2726	2798		CHASE

INVOICED  
DATE 2-12-09  
INV. NO. 2009061199

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 05 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED  
FEB - 3 2009  
KCC DODGE CITY

Signed

Jerry W. Stapleton  
(TECHNICIAN)  
PART II

PT