

15-051-25153-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25153-00-00  
Spot: S2NWNW Sec/Twnshp/Rge: 1-11S-20W  
4268 feet from S Section Line, 4768 feet from E Section Line  
Lease/Unit Name: HELEN A Well Number: 1  
County: ELLIS Total Vertical Depth: 3676 feet

Operator License No.: 6194  
Op Name: E S P DEVELOPMENT, INC.  
Address: 17746 177TH BOULEVARD  
PARADISE, KS 67658

Conductor Pipe: Size feet: 119.47  
Surface Casing: Size 8.625 feet: 234  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 08/28/2002 11:30 AM  
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC  
Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 08/28/2002 2:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3666' w/25 sxs.  
2nd. Plug at 1550' w/25 sxs. Anhydrite 1500' - 1550'.  
3rd. Plug at 800' w/100 sxs. Dakota 494' - 794'.  
4th. Plug at 285' w/40 sxs. Surface pipe to 234'.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.


RECEIVED  
9-17-2002  
SEP 17 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed   
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-18-02

WV. NO. 2003060521

SEP 16 2002