

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-01-088-00-01

SW SW SW /4 SEC. 13 , 11 S, 20 W  
330 feet from S section line  
330 feet from E section line

Operator license# 5663

Lease: Schoenthaler Well # 2

Operator: Hess Oil Company

County Ellis

115.24

Address: P.O. Box 1009  
McPherson, Kansas 67460

Well total depth 3546, p**bt**d 3503 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 13 Inch @ 116 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Allied Cement Co. License#     

Address: Russell, Kansas

Company to plug at: Hour: 8:00 Day: 22 Month: April Year: 1993

Plugging proposal received from: Brian Hess

Company: Hess Oil Company Phone: 316-241-4640

Were: 5 1/2" casing set @ 3557' w/250 sx cmt: Perf. @ 3320-3462'; Base of Salt Sec. & 50' @ 2300; Mid-Anhy. @ 1522'; Base of Dakota & 50' @ 700'; Base of S.P. @ 116';

Order 225 sx 60/40 pozmix, 10% gel with 1/2 lb. f.c. & 500# hulls, 10 sx gel

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 16:30 , Day: 22 , Month: April , Year: 1993

Actual plugging report: spotted 25 sx cmt w/200# hulls @ 3462'; pumped 18 bbls. water; spotted 25 sx cmt @ 2300; shot casing at 1513; pumped 10 sx gel & 90 sx cmt w/250# hulls; pumped 2 bbls water; shot casing @ 700, pumped 40 sx cmt, circ. to surf; pumped 2 bbls water; pulled to 160', circ to surf.; pulled last 5 joints.

As per directions KCC District 4 office

Remarks: Allied Cementing (Russell)  
Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X NO       
Plugged through TUBING     , CASING X. Elevation: 2015

I did[ X ] / did not[      ] observe the plugging.

Kew Kew  
(agent)

INVOICED

DATE 5-14-93

INV. NO. 37708

4-22

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1993  
CONSERVATION DIVISION  
Wichita, Kansas