

15-051-23453-00-00 ✓

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23, 453

C-SE-SE, Sec. 13, T 11 S, R 20(W)

660 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name ELLA-2" Well # 1-13

Operator: MURFIN DRUG. CO.
Name & Address: 617 UNION CTR. BLDG.
WICHITA, KANS. 67202

County ELLIS

Well Total Depth 3638 feet 118.24

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor MURFIN DRUG. CO License Number 316-267-3241

Address 617 UNION CTR. BLDG., WICHITA, KANS. 67202

Company to plug at: Hour: 8:00 PM Day: 10th Month: MAY Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO LOYD DELLETT.

(company name) MURFIN DRUG. (phone) 316-267-3241

were: 8 5/8" - 282 FT SP. CUM 1175 ST SUN SET (BY SUN OUT)
ORDERED 185 ST 20/50 FORMIX 4% GEL-3% CA-CL AND 8 5/8" PLUG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
TOP OF ABRUCABLE @ 3622 FT EW. 2003 ANHY. 1382

Signed *Marion Schmidt*
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:15 PM Day: 10th Month: MAY Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 185 ST 20/50 FORMIX 4% GEL-3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1st PLUG @ 3600 FT 20 ST CMT., 2nd PLUG @ 1390 FT 25 ST CMT.
3rd PLUG @ 1120 FT 80 ST CMT., 4th PLUG @ 300 FT 40 ST CMT.
5th PLUG SOLID BRIDGE HULL'S - PLUG @ 40 FT 10 ST CMT., 10 ST RAT WBLE (CIRCULAR)

Remarks: CEMENTED BY HALLIBURTON CMT.

I hereby certify that the above plugging instructions were given as herein stated and that I () / did not) observe this plugging.

Signed *Marion Schmidt*
(TECHNICIAN) DOIC

FORM CP-2/3 Rev. 9-82

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 5-19-83 MAY 16 1983

INV. NO. 4365-6 CONSERVATION DIVISION Wichita, Kansas