

8-14

4-041511

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,818-00-00

NW /4 SEC. 13, 11 S, 20 W
4780 feet from S section line
3840 feet from E section line

Operator license# 5663

Lease Mixer well # 2

Operator: Hess Oil Company

County Ellis

Address: P.O. Box 1009
McPherson, Kansas 67460

Well total depth 3297 feet ^{107.15}
Conductor Pipe: 39 inch @ cwc feet
Surface pipe 8 5/8 Inch @ 209 feet
CWC.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:00P.M Day: 14 Month: August Year: 93

Plugging proposal received from: Jamie Hess

Company: Hess Oil Company Phone:

Were: 5 1/2" casing set @ 3497' w/150 sxs. cement. C.I.B.P. @ 3340'. Sand to 3280' with 5 sxs. cement on sand. Recovered 2195' of 5 1/2" casing. Ordered 175 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 200# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M, Day: 14, Month: August, Year: 93

Actual plugging report: Plugged thru casing as follows: spotted 35 sxs. @ 2140'. 25 sxs. @ 1425'. 65 sxs. and 100# hulls @ 700'. 40 sxs. @ 250' circulate to surface. Capped with additional 10 sxs. cement.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X did not observe the plugging.

Dennis L. Hamel

(agent)
Form CP-2/3

INVOICED
10-4-93
38852

RECEIVED
STATE CORPORATION COM
OCT 04 1993
CONSERVATION DIVI
Wichita, Kansas