

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21528-00-00
Spot: NENWNWNE Sec/Twnshp/Rge: 32-32S-20W
150 feet from N Section Line, 2050 feet from E Section Line
Lease Name: FRINK UNIT A Well #: 1
County: COMANCHE Total Vertical Depth: 5250 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.38	372		WITH 950 SX CMT
PROD	5.5	5245	4040	WITH 100 SX CMT
SURF	8.625	732		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2009 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT TO 5000'. LOAD HOLE WITH GEL WATER. PUMP 50 SX CMT AT 750'. PLUG AT 390' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT. FILL 8 /58" X 13 3/8" ANNULUS. CHECK TO 500 PSI.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2009 5:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 200# HULLS & 30 SX CMT AT 5000'. TAGGED TOC @ 4885'. 1ST PLUG PUMP 15 SX GEL, 100# HULLS, & 50 SX CMT AT 750'. 2ND PLUG PUMP 100# HULLS & 50 SX CMT AT 390'. 3RD PLUG PUMP 20 SX CMT AT 40'. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5190	5195		
5168	5172		
5164	5168		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 12 2009
CONSERVATION DIVISION
WICHITA, KS

NVOICED

DATE 2-18-09
INV. NO. 2009061224

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED

FEB - 6 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
PKT

(TECHNICIAN)

Form CR 228

PKT