

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05046-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 29-20S-5W
3316 feet from S Section Line, 5075 feet from E Section Line
Lease Name: BRIGGS Well #: 1
County: MCPHERSON Total Vertical Depth: 3381 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3350		175 SX
SURF	10.75	160		125 SX

109.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2009 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVE WERTZ Witness Type: NONE
Date/Time Plugging Completed: 02/02/2009 11:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3300' AND CAP WITH 7 SX'S CEMENT. PERFORATE @ 800', 430' AND 250'. RUN TUBING TO 800' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 430' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 280 SX'S TOTAL.

Perfs:

INVOICED
DATE 2-18-09
INV. NO. 2009061226

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-33243. LOG TECH TICKET #5612.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKT