

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05100-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 31-20S-5W
2970 feet from S Section Line, 1980 feet from E Section Line
Lease Name: A C JOHNSON Well #: 3
County: MCPHERSON Total Vertical Depth: 3381 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3316		
SURF	10	160		<u>109.88</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2009 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 02/04/2009 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND 50' OVER PERFS TO 3250' AND CAP WITH 7 SX'S CEMENT. PERFORATE @ 750' AND 250'. RUN TUBING TO 750' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 200 SX'S TOTAL.

Perfs:

INVOICED
DATE 2-18-09
INV. NO. 2009 061226

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 13 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ 4% GEL. COPELAND TICKET #35281. LOG TECH TICKET #5626.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

PCT