

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-05101-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 31-20S-5W
330 feet from N Section Line, 1980 feet from E Section Line
Lease Name: A C JOHNSON Well #: 4
County: MCPHERSON Total Vertical Depth: 3358 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3350		200
SURF	12	146		110

109.14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/05/2009 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3300' AND CAP WITH 6 SX'S CEMENT. PERFORATE @ 750' AND 250'. RUN TUBING TO 750' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 220 SX'S.

Perfs:

INVOICED
DATE 2-18-09
INV. NO. 2009061226

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 13 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-35282. LOG TECH TICKET #5612.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)