

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21555-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 21-12S-20W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BITTEL Well #: 2
County: ELLIS Total Vertical Depth: 3890 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| PROD | 5.5 | 3889 | 0 | w/100 sxs cmt |
| SURF | 8.625 | 207 | 0 | w/120 sxs cmt |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2009 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shoot two hole perf at 1575' and 900'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2009 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report: 20080062002 - Control #

02/05/2009 - Poe drilled with mud pump and swivel to 1585'. Ran into wood and iron bridge.
02/06/2009 - Perf Tech shot two hole perms at 1575' and 900'.
Poe Well Service RIH with tubing to 1545'.
Allied rigged to tubing - pumped 165 sxs 60/40 pozmix - 4% gel to circulate cement to pit area.
Pulled tubing. Allied rigged to 5 1/2" casing with a swedge - pumped 80 sxs cement with 300# hulls.
Max. P.S.I. 150#. S.I.P. 100#.
Rigged to 8 5/8" - pumped 5 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3822 | 3839 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 12 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34941.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

FEB 09 2009

[Signature]

N-B CO., INC.
 BOX 506, RUSSELL, KS. 67665

#2 BITTEL

21-12-20W
 SW SW NW

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOL _____ FIELD DIST 57 NORTH

E 2225 KB CM 9/3/78 CARD ISSUED 12/21/78 P 35 BOPD

~~ARB~~ 3822-3839 OA

API 15-051-21,555

| | | | |
|---|---|---|---|
| | + | + | + |
| • | + | + | + |
| | + | + | + |

| LOG | TOPS | DEPTH | DATUM |
|-------------|------|-------|-------|
| TOP | | 3255 | -1030 |
| HEEB | | 3483 | -1258 |
| TOR | | 3506 | -1281 |
| LANS | | 3522 | -1297 |
| B KG | | 3759 | -1534 |
| MARM | | 3818 | -1593 |
| *ARB | | 3886 | -1661 |
| TO | | 3890 | -1665 |
| *SAMPLE TOP | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 207/120 SX, 5" 3889/100 SX
 DST (1) 3827-45/45-45-45-45, REC 130'
 FROGGY O (SOME FO), SIP 1120-1067#,
 FP 53-53#, 64-86#
 MICT - CO, PF 36/3822-3839 OA, AC
 4500 GAL, POP, P 35 BOPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS