



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
-10-07-1982
OCT 07 1982
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-167-21986-00-00

Dear Sir:

Mr. Berton Beery of Shields Drilling Co. #236 has this

date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg, Russell, Ks. 67665 #5184

Lease Name: Strecher Well No. 3

Location: NE-SE-NE Sec. 31 Twp. 11 Rge. 12 (E) (W)

County: Russell Total Depth: 3250'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Beery was instructed to plug the well as follows:

8 5/8" - 406' S.P. cas. w/ 250 sacks common - 2% Sol. - 3% Cal. Cl.

Ordered 150 sacks 5/8" permix - 4% Sol. - 3% Cal. Cl. + 8 5/8" plug. Spot w/ drill stem
w/ heavy mud between all plugs. 1st plug. C 660' w/ 80 sacks.

2nd plug C 450' w/ 40 sacks.

3rd plug - solid bridge of hulls + plug C 40' w/ 10 sacks.

Circulate 10 sacks in rat hole + 10 sacks in mouse hole

Very truly yours,

Bill G. Smith
Conservation Division Agent