

15-167-21845-00-00

FORM CP-2

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Vern Zorn of Shields Oil Producers Inc has this date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers Inc.

Complete Address: Shields Bldg. Russell, Ks. 67665

Lease Name: Strecker Well No. 1

Location: NE NE NW Sec. 31 Twp. 11 Rge. 12 (E) (W)

County: Russell Total Depth: 3455'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereafter indicated: \_\_\_\_\_

Mr. Vern Zorn was instructed to plug the well as follows:

8 5/8" 270' S.P. cuc. W/ 160 sacks common 2% Gel-~~8~~% Cal.Cl.

Ordered 135 sacks 50/50 posmix 4% Gel-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 690' W/ 70 sacks cement

2nd plug @ 270' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks cement in rat hole, and 5 sacks cement in house hole.

Very truly yours,

  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
01-11-1982  
JAN 11 1982

CONSERVATION DIVISION  
Wichita, Kansas