



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
10-07-1982
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-167-21897-00-00

Dear Sir:

Mr. Bill Chance of Rains & Williamson Oil Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Co., Inc.

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kas. 67202

Lease Name: Thompson Well No. 1

Location: SE NW SE Sec. 7 Twp. 11 Rge. 14 (E) (W)

County: Russell Total Depth: 3540'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Chance was instructed to plug the well as follows:

8 5/8" - 242' S.P. cas. w/ 165 sacks common - 2% Sol. - 3% Cal. Cl.
Ordered 140 sacks 50 permit - 4% Sol - 3% Cal. Cl. + 8 5/8" plug spot w/ drill stem w/
heavy mud between all plugs. 1st plug @ 660' w/ 80 sacks.
2nd plug @ 250' w/ 40 sacks.
3rd plug - Solid bridge of shells & plug @ 40' w/ 10 sacks.
Circulate 10 sacks in rat hole

Very truly yours,

Ruth G. Leibel
Conservation Division Agent