

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217
 RECEIVED
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

DEC 2 1974
 13-02-1974
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

15-167-207 09-00-00

Dear Sir:

Mr. Elmer Zimmerman of Woodman & Iannitti Drlg. Cohas this date requested permission to plug the following described well:

Mr. Vincent F. Hiebsch guarantees payment of the plugging fee.

Operator's full Name: Vincent Oil Corporation

Complete Address: 719 Union Center Bldg., Wichita, Kansas

Lease Name: Hackmeister Well No. # 1

Location: W/2 SW SW Sec. 4 Twp. 11 Rge. 15 (E)(W) W

County: Russell Total Depth 3410 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Elmer Zimmerman was instructed to plug the well as follows:

8 5/8" csg. 207' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Sun Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don L. ...
 Conservation Division Agent