



15-051-22785-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1982
CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Aom of Pioneer Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill, Plainville, Ks. 67663

Lease Name: Potter Well No. 1

Location: C of S/2 SE NW Sec. 32 Twp. 11 Rge. 16 (E) (W)

County: Ellis Total Depth: 3505'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Aom was instructed to plug the well as follows:

8 5/8"-255' S.P. cuc. w/140 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

April 28, 1982

INVOICE NUMBER: 74-W

TO: Liberty Enterprises, Inc.
308 W. Mill
Plainville, KS., 67663

PAYABLE UPON RECEIPT
PAID UPON RECEIPT

PLUGGING ASSESSMENT AS FOLLOWS:

Potter #1
C 3½ SE NW, Sec. 32-11S-16W \$113.91
Ellis
T.D. 3505'

Pioneer Drilling Co., Inc.

NOTE: We also need the following before our file is completed:

- x _____ Well Plugging Record (CP-4)
- x _____ Well Log
- x _____ Well Plugging Application (CP-1)


WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

Administrator



Mr. Gil Scheck, 2202 Canterbury Rd., Hays, KS., 67601, (913) 628-2600

is hereby assigned to supervise the plugging of the above mentioned well.