



15-051-22993-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ken Fox of Pioneer Drlg. Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill, Plainville, Ks. 67663

Lease Name: Simpson "A" Well No. 2

Location: C w/2 NW SW Sec. 3 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3510'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Fox was instructed to plug the well as follows:

8 5/8"-225' S.P. cuc. w/150 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
5-3-1982
MAY 3 1982
CONSERVATION DIVISION
Wichita Kansas