

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22141-00-00
Spot: NESESWNW Sec/Twnshp/Rge: 31-17S-29W
2050 feet from N Section Line, 1190 feet from W Section Line
Lease Name: DOWD Well #: 31-1
County: LANE Total Vertical Depth: 4644 feet

Operator License No.: 34158
Op Name: O'BRIEN RESOURCES, LLC
Address: PO BOX 6149
SHREVEPORT, LA 71136

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 235 | | WITH 180 SX CMT |

150.93

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/17/2008 12:00 AM
Plug Co. License No.: 34190 Plug Co. Name: VISION OIL & GAS SERVICES LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 35 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 12/17/2008 2:25 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 715' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 35 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED
DATE 2-12-09
INV NO. 2009061196

KANSAS CORPORATION COMMISSION

FEB 04 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP


District: 01

RECEIVED

JAN 29 2009

KCC DODGE CITY

Signed



(TECHNICIAN)

