

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Anderson Energy, Inc.  
Address: 221 S. Broadway Suite 302  
Phone: (316) 263-1006 Operator License #: 6484  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1-17-09 (Date)  
by: Case Morris (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing/Kansas City Depth to Top: 3516 Bottom: 3708' T.D. 3889"  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 065-22,509-0000  
Lease Name: Mary Rush  
Well Number: 9-16-1  
Spot Location (QQQQ): \_\_\_\_\_ - NE - SE - SE  
990 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 9 Twp. 6 S. R. 22  East  West  
County: Graham  
Date Well Completed: 4-11-90  
Plugging Commenced: 2-3-09  
Plugging Completed: 2-3-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing/Kansas City	Oil/Water	3667'	3669'	8 5/8"	217'	None
				4 1/2"	3873'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked to 4 1/2" Casing and Mixed 50 sxs. 60/40 Poz. 4% Gel with 200# Halls. Followed with 160 sx. 60/40 Poz, 4% Gel.  
Pressured to 500# and shut in with 500#. Tied to 8 5/8" Casing and mixed 2 sxs. and pressured to 150#. Released  
both 4 1/2" and 8 5/8" Casing and cement stayed at surface.

Name of Plugging Contractor: Allied Cementing and Acidizing, Inc. License #: 99996  
Address: P. O. Box 32 Russell, Kansas 67665  
Name of Party Responsible for Plugging Fees: Anderson Energy, Inc.  
State of Kansas County, Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry W. Piesker  
(Address) P.O. Box 177 Victoria, Kan. 67671

SUBSCRIBED and SWORN TO before me this 4th day of FEBRUARY, 2009  
Patricia Dreiling  
Notary Public My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2073, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 05 2009  
CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten initials]*