

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: T-N-T Engineering, Inc.
Address: 3711 Maplewood, Suite 201, Wichita Falls, TX 76308
Phone: (620) 786-5514 Operator License #: 33699

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Doug Louis (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
LKC G Depth to Top: 3060 Bottom: 3086 T.D. _____
LKC J Depth to Top: 3158 Bottom: 3168 T.D. _____
Arbuckle Depth to Top: 3275 Bottom: 3325 T.D. 3325

API Number: 15-159-02472-00-00

Lease Name: H Roth

Well Number: 5

Spot Location (QQQQ): NE - NE - NE - NE *nw* *KCC DIST PER UPS*

Feet from North / South Section Line

Feet from East / West Section Line

Sec. 29 Twp. 19 S. R. 10 East West

County: Rice

Date Well Completed: 8-52

Plugging Commenced: 5-29-07

Plugging Completed: 6-1-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		<u>0</u>	<u>452</u>	<u>8 5/8"</u>	<u>452'</u>	<u>—</u>
		<u>0</u>	<u>3282</u>	<u>5 1/2"</u>	<u>3282'</u>	<u>1640'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 2990', bailed 5 sacks cement with bailer, had 14" stretch, ripped casing at 1860', worked pipe, ripped casing at 1640', pipe came free, pulled casing up to 1250', pumped 35 sacks 150# hulls at 1250', pulled to 900', pumped 35 sacks 150# hulls, pulled to 500', circulated with 130 sacks, 100# hulls, pulled rest of casing, tore down floor and rig, emptied pit, cleaned up location.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 U.S. Hwy 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: T-N-T Engineering, Inc.

State of Texas County, Wichita, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Hal Gull

(Address) 3711 Maplewood, Ste. 201, Wichita Falls, Tx 76308

SUBSCRIBED and SWORN TO before me this 5th day of February, 2009

Sworn A. VanHuss My Commission Expires: May 26 2010
Notary Public



RECEIVED
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION
WICHITA, KS

RGF