

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Pratt Well Service, Inc.

Address: PO Box 907, Pratt, Kansas 67124

Phone: (620) 672-9571 x5 Operator License #: 5893

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-033-20813-00-00

Lease Name: Burkhall

Well Number: 2

Spot Location (QQQQ): NE - NW - SW -

2310 Feet from  North  South Section Line

4290 Feet from  East  West Section Line

Sec. 17 Twp. 31 S. R. 18  East  West

County: Comanche

Date Well Completed: 02-28-91

Plugging Commenced: 1-22-09

Plugging Completed: 1-28-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	638	
				5 1/2	5180	2885

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 09 2009  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Changed over for rods, pulled rods, changed over for tubing, pulled tubing, rigged up floor, hooked up to 5 1/2" casing, pumped 25 sacks, 100# hulls, displaced to 4730', max pressure 300, shut in 150 psi, tagged cement at 4730', pulled slips, had 24" inches stretch, cut surface off 4' below ground, ripped casing at 3050', worked pipe, ripped casing at 2885', pipe came free, pulled casing up to 1050', pumped 15 gel, 50 sacks, 100# hulls at 1050', pulled to 660', pumped 50 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface, tore down floor and rig, emptied water out of cellar, cleaned up location.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67524

Name of Party Responsible for Plugging Fees: Pratt Well Service, Inc.

State of KANSAS County, PRATT, ss.

Kenneth C. Gates (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenneth C. Gates

(Address) P.O. BOX 907 PRATT, KS 67124

SUBSCRIBED and SWORN TO before me this 6<sup>th</sup> day of February, 2009

**JANIS S. PARSONS**  
Notary Public - State of Kansas  
My Appt. Expires 10-01-2011

Janis S. Parsons My Commission Expires: 10-01-2011  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRATT