

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

* Corrected TD
2-5-09

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bowman Oil Company
Address: 805 Codell Road Codell, Kansas 67663
Phone: (785) 434-2286 M-F Operator License #: 6931
Type of Well: Oil - Dry Hole, Plugged (OWWO) Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 12-4-2008 (Date)
by: Case Morris - KCC District #4, Hays, Kansas (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3303' Bottom: _____ T.D. 3558'
B Kansas City Depth to Top: 3508' Bottom: _____ T.D. 924'
Arbuckle Depth to Top: 3547' Bottom: _____ T.D. _____

API Number: 15 - 163-19324-0002
Lease Name: Jelinek
Well Number: #2 (OWWO)
Spot Location (QQQQ): _____ - SE - NE - SE
1650' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 23 Twp. 9 S. R. 19 East West
County: Rooks County, Kansas
Date Well Completed: (Originally 5-18-48) 12-4-2008
Plugging Commenced: 12-4-2008
Plugging Completed: 12-4-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	256'	8 5/8"	256' (5-18-48)	0'
		1287'	3546' <u>924'</u>	5 1/2"		0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Washed Hole down to 924' and Hit Iron. 256' of 8 5/8" Surface, 7 7/8" Hole to 924', Run 2 7/8" tubing to 912' & Spotted 100 sxs cement, Pulled up to 300' and spotted 40 sxs cement. Pulled up to 60' and Circulated cement to Surface, Hole Stayed Full.
90 sxs Common and 60 sxs 60/40 Pozmix, 4% Gel, a Total of 150 sxs.

See Attached - Original Well Plugging Record, Well Log and Card

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Allyed Cementing Company, LLC License #: 6931

FEB 09 2009


Address: P.O. Box 31 Russell, Kansas 67665

CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Bowman Oil Company

State of Kansas County, Rooks, ss.

Louis "Don" Bowman (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Louis "Don" Bowman
(Address) 805 Codell Road, Codell, Kansas 67663
and SWORN TO before me this 6th day of January, 2009
Louis M. Bowman My Commission Expires: May 28, 2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

sent 1-9-09 *[Handwritten initials]*