

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/15/09 (Date)
by: Duane Krueger (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 1954 Bottom: 1960 T.D. _____
Hepler Depth to Top: 2188 Bottom: 2212 T.D. _____
Simpson Depth to Top: 2500 Bottom: 2504 T.D. 2564

API Number: 15 - 015-20717 - 00-00
Lease Name: Knox A
Well Number: 50
Spot Location (QQQQ): _____ - NE - NW - NW
330 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 22 Twp. 25 S. R. 05 East West
County: Butler
Date Well Completed: 2/18/75
Plugging Commenced: 1/16/09
Plugging Completed: 1/16/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	sw	1954	1960	8-5/8"	219	0
Hepler	sli oil & sw	2188	2212	5-1/2"	2564	0
Simpson	Sli oil & sw	2500	2504			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 1945', spot 50 sx Class A, 3% cc, let set 1-1/2 hrs; wireline tag @ 1601', pressure test casing to 300#;

Tubing to 280, mix and pump 40 sx Class A, Circulate cement to surface. TOOH

Complete 1/16/09 - noon - Consolidated Ticket #20510

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Simmons Well Service, Inc. License #: 32991

JAN 21 2009

Address: 6730 SE Satchell Creek Road, Leon, KS 67074

CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Casey Coats

(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 19th day of January

Michelle D. Henning
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKA