

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Roberts Resources, Inc. Address: 520 S. Holland - Suite 207, Wichita KS 67209 Phone: (316) 721-2817 Operator License #: 32781 Type of Well: Oil & Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 01/05/09 (Date) by: Eric MacLaren (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No Producing Formation(s): List All (If needed attach another sheet) Mississippi Depth to Top: 5024 Bottom: 5056 T.D. 5104 Altamont Depth to Top: 4882 Bottom: 4884 T.D. 5000

API Number: 15 - 097-21224-00-01 Lease Name: Emerson-Caraway Trust KCC DIST per CP213 Well Number: 1 Spot Location (QQQQ): NW - NE - NE SW 46204528 Feet from [] North / [X] South Section Line 1980 2068 Feet from [X] East / [] West Section Line Sec. 32 Twp. 30 S. R. 18 [] East [X] West County: Kiowa Date Well Completed: 11/19/1986 Original Date Plugging Commenced: 01/07/2009 Plugging Completed: 01/07/2009

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Surface, water, 0, 617, 8 5/8, 617, none. Row 2: 0, 4902, 4 1/2", 4902, 2822.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 4830' w/ 2 sacks cement on top. Shot casing off @ 2822 and pulled. 15 sx gel & 50 sx cement @ 1150'. 50 sx cement @ 550'. 20 sx cement @ 60' and circulated to surface. 60/40 poz 4% gel

Name of Plugging Contractor: H2 Plains, LLC License #: 4072 33645 Address: PO Box 346 Ness City KS 67650

RECEIVED KANSAS CORPORATION COMMISSION JAN 29 2009 CONSERVATION DIVISION WICHITA, KS

Name of Party Responsible for Plugging Fees: Roberts Resources, Inc. State of Kansas County, Sedgwick, ss.

Kent Roberts (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kent Roberts

(Address) 520 S. Holland Suite 207 Wichita KS 67209

Notary Public: CONNIE R. RICHARDSON, NOTARY PUBLIC, STATE OF KANSAS, My Commission Expires: 12-12-11

Handwritten initials/signature in bottom right corner.