

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rosewood Resources, Inc.
Address: 2711 N. Haskell Ave., Suite 2800, LB 22
Phone: (970) 324-1686 Operator License #: 33019
Type of Well: Gas DH KCCPCT DEICP 2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Darrel Dipman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Niobrara Depth to Top: 1360' Bottom: 1402' T.D. 1600'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 023-21114-00 -00
Lease Name: Isernhagen
Well Number: 21-25
Spot Location (QQQQ): SE SW NE NW
357488 Feet from North / South Section Line
1875 2234 Feet from East / West Section Line
Sec. 25 Twp. 3S S. R. 41 East West
County: Cheyenne
Date Well Completed: 10/28/08
Plugging Commenced: 10/28/2008
Plugging Completed: 10/28/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Ogallala	Water	Surface	333'	7"	8 jts	
Niobrara	Gas	500'	1600'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug 1400' -- 1160' down the 4 1/2" csg w/ 50 lbs cotton seed hulls & 40 sks #1 Neat cmt
2nd Plug 450'-- 215' w/ 40 sks #1 Neat cmt
3rd Plug 100' to surf. w/ 10 sks #1 Neat cmt

Name of Plugging Contractor: Advanced Drilling Technologies LLC License #: 33532
Address: PO Box 203, Yuma, Colorado, 80759

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 29 2009
CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Rosewood Resources, Inc.
State of Kansas County, Cheyenne, ss.

Wayne Mahon (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Wayne Mahon
(Address) PO Box 926, St. Francis, KS 67756

SUBSCRIBED and SWORN TO before me this 22 day of January 2009
Kathy Roelfs My Commission Expires: 6-3-09
Notary Public

NOTARY PUBLIC - State of Kansas
KATHY ROELFS
My Appt. Exp. 6-3-09

KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials