

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 35-39

LOCATION NW NW NE

SEC. 24 TWP. 9 RGE. 23

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. RA-1 Lease Mine Mire B

Operator Petroleum Management Address 810 Cent Bldg Wichita,

Field _____ County Graham

Total Depth 4168 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 157' circulated with cement - 5 1/2" at 3892' with 125

sax cement behind - perforated at 3834.

Filled with sand to 3820', set 4 sax cement with dump bailer,

pulled 3065' 5 1/2" - filled with mud to 157', set rock and 15 sax

cement, mud to 35', set rock and 10 sax cement to bottom cellar.

Edna Perry
District Conservation Agent

2-14-56

Date 2-12-56

PLUGGING

FILE SEC 24 T 9 R 23 W
BOOK PAGE 384 LINE 39

CP-3