

14 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
5-23-66
MAY 23 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling, Incorporated,

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name LaCerte Well No. 2

Location CSE-NW Sec. 25 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3950

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 10:30AM Day 19 Month 5 Year 1966

The Above well was plugged as follows:

211'--8 5/8" Surface pipe, cement circulated,
3921'--4 1/2" Production casing cemented with 100 Sx. Top perforations @
3872.

Sanded well back to 3850' and set 3 Sx. cement with dump bailer.
Pulled 4 1/2" to 600' and circulated heavy gel mud. (Used 16 Sx. gel).
Pulled 4 1/2" to 540' and displaced 20 Sx. cement thru 4 3/8". Pulled 4 1/2" to
240' and displaced 20 Sx. cement thru 4 1/2". Pulled 4 1/2", set rock bridge
@ 35' and 10 Sx. cement to bottom of cellar.

(Recovered 2498'--4 1/2" Production casing)

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 5-23-66
INV. NO. 2251-W