

15-065-03116-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1965

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Woodman and Iannitti Oil Company,  
Complete Address: 706 Union National Building, Wichita, Kansas.  
Lease Name Lacerte Well No. 1  
Location CS/2-SW-SW Sec. 25 Twp. 9 Rge. (E) (W) 23  
County Graham Total Depth 3924  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,  
Address: Box #562, Great Bend, Kansas. License No. 574  
Operation Completed: Hour 5:30PM Day 22 Month 9 Year 1965

The Above well was plugged as follows:

181'--8 5/8" Surface pipe, cement circulated.  
3924'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to  
3905'. Top perforations @ 3732'.

Pushed plug to 3680', sanded back 25' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2", set bridge @ 400' and filled hole with Redi-Mix cement using  
5 1/2 yards. (Recovered 1019' 5 1/2" casing) (WaKeeney Redi-Mix)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

9/29/65

INV. NO.

1869-u

Signed:

W. L. Nichols  
Well Plugging Supervisor