

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
6-6-66  
JUN - 6 1966  
CONSERVATION DIVISION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Dane G. Hansen Trust,  
Complete Address: Logan, Kansas.  
Lease Name LaCerte Well No. A-5  
Location Appr. SW-NW-SE Sec. 25 Twp. 9 Rge. (E) (W) 23  
County Graham Total Depth 3904  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: G & G Drilling Company,  
Address: 107 Rule Building, Wichita, Kans. License No.       
Operation Completed: Hour 8:30PM Day 30 Month 5 Year 1966

The Above well was plugged as follows:

192'--8 5/8" Surface pipe, cement circulated with 140 Sx.  
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.  
cement thru DP. Heavy mud to 190', set plug with 1/4 sk. hulls and dis-  
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sk.  
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated:

Signed: A. L. D. [Signature]  
Well Plugging Supervisor

INVOICED

DATE 6/6/66  
INV. NO. 3349-W