

15-065-30189-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Dane G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name Hill City High School Well No. 9

Location Appr. CNL-SE/4 Sec. 26 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3940

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C & G Drilling Company,

Address: 107 Rule Building, Wichita, Ks. License No.

Operation Completed: Hour 6:45PM Day 20 Month 5 Year 1966

The Above well was plugged as follows:

193'--8 5/8" Surface pipe, cement circulated with 140 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 190', set plug and displaced 20 Sx. cement

thru DP. Heavy mud to 40', set plug with 1/2 sk. hulls and 10 Sx. cement

to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/26/66
INV. NO. 3295-U

Signed: M. L. Nichols
Well Plugging Supervisor