



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SW

SEC. 26 TWP. 9 RGE. 23

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Sparks _____

Operator Burch Drg Co Inc. Address 1011 Union Center Wichita, Kans

Field _____ County Graham

Total Depth 4529 Feet.

Plugging Contractor same

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at
600', displaced 20 sax cement through drill pipe, heavy mud to 200',
set cementing plug and displaced 20 sax cement through drill pipe,
heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement
to bottom cellar.

District Conservation Agent

Date 9-10-57

Received
KCC
9-13-57

PLUGGING
FILE SEC. 26 T. 9 R. 23 W
BOOK PAGE 45 LINE 18