

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-2-65
AUG 2 - 1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil of Kansas
Complete Address: 2318 Washington St - Mt Bend, Kansas
Lease Name Ameron Well No. 1
Location SE - SW - NW Sec. 31 Twp. 9 Rge. 23 (E) (W)
County Groham Total Depth 4050
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Pulling Co.
Address: Ellenwood, Kans License No. 399
Operation Completed: Hour 11am Day 21 Month July Year 1965

The Above well was plugged as follows:

T.D. - 4050 - 8 5/8 - 229-cw@17504 - 4 1/2 - 4049 - 150.cw@. - Perfs - 3926 - 3989
Squeeze job - No Pipe recovery - Hooked pump truck to
4 1/2" pipe and squeezed 10 sac cement - followed by 24 sac
Jell Mud, followed with 40 sac cement, and let set overnight
with 500 lbs pressure. Next morning, removed cap and squeezed
8 5/8 pipe with 6 sac Jell Mud and 24 sac cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/2/65
INV. NO. 1562-U

Signed: Delbert P. Luter
Well Plugging Supervisor