

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECORDED
STATE CORPORATION COMMISSION
3-8-71
MARCH 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,
Complete Address Drawer #370, Hays, Kansas.
Lease Name J. B. Cameron Well No. 1
Location NE-NE-NW Sec. 31 Twp. 9 Rge. (E) (W) 23
County Graham Total Depth 3838'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dreiling Oil, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 12:00 M Day 3 Month 3 Year 1971

The above well was plugged as follows:

203'--8 5/8" Surface, cement circulated with 160 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INV. NO. 3406-W
3/8/71