

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-20,341

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Drilling Oil Inc (Bill Draper)

Complete Address Rt. 1 Victoria, Kansas

Lease Name Justis Well No. B-1

Location SW-SE-NW Sec. 32 Twp. 9 Rge. 22 (East) (West)

County Arkham Total Depth 4060

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Inc

Address Russell, KS License No. _____

Operation Completed: Hour: 2:30pm Day: 12 Month: 5 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" set @ 155' w/150 sx - Circ Cmt -
4 1/2" set @ 4059' w/170 Perfs @ 3390-93, 3976-80, 3954-57,
3867-70, 3856-60 - Cast plug @ 3750 w/50' sand &
5 sx cmt on top - Ordered 140 sx 5/8" pozmix bagel 32cc 25gal
5 hulls + 8 5/8" Plug -> pumped in 4 hulls -> 12 gal -> 1 hull ->
70 cmt, 12 gal, Red plug -> 70 cmt. Recovered 1075' of 4 1/2"
P.S.I. 300 # (Allied)

Amount of Surface Casing: 155' 178' RT KCC

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
5-17-82
MAY 17 1982

INVOICED
SIGNED: _____
Conservation Division Agent
Wichita, Kansas
DATE 5-19-82
183-u
184



Patch II

15-065-20417-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 - 74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. 32, Victoria, Kansas.

Lease Name Butcher Well No. B-2

Location W/2-NE-SE Sec. 32 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 4035'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 1 Month 2 Year 1974

The above well was plugged as follows:

191'--8 5/8" Surface casing, cement circulated with 150 Sx.
4029'--4 1/2" Production casing cemented on bottom with 175 Sx. No plug-back indicated.
Top perforations from 3954' to 3957'.
Pushed plug to 3850', sanded well back to 3800' and set 4 Sx. cement with dump bailer.
Pulled 4 1/2" casing (1128') and squeezed well initially with 5 sacks hulls and 7 sacks
gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 15 sacks gel from
825' to 200' and followed with 30 Cu. Ft. cement from 200' to 125' then 3 sacks gel
from 125' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum
pump-in pressure--500#. Final shut-in pressure 150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. S. Dehler
Well Plugging Supervisor

DATE 2/5/74

INV. NO. 8501-W