

15-065-20317-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
2-4-74  
FEB 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. 32, Victoria, Kansas.

Lease Name Butcher Well No. B-1

Location SW-NW-SE Sec. 32 Twp. 9 Rge. (E) (W)23

County Graham Total Depth 4030'

Abandoned Oil Well       Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Sun Oil Well Cementing, Incorporated,

Address Box #69, Hays, Kansas. License No.     

Operation Completed: Hour 2:00 PM Day 1 Month 2 Year 1974

The above well was plugged as follows:

192'--8 5/8" Surface casing, cement circulated with 175 Sx.  
4029'--4 1/2" Production casing cemented on bottom with 175 Sx. Top of cement @ 3300'.  
No plug-back indicated. Top perforations from 3953' to 3958'.  
Pushed plug to 3850', sanded back to 3800' and set 4 Sx. cement with dump bailer.  
Pulled 4 1/2" casing (1120') and squeezed well initially with 5 sacks hulls and 7 sacks  
gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 15 sacks gel from  
825' to 200' and followed with 30 Cu. Ft. cement from 200' to 125' then 3 sacks gel  
from 125' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum  
pump-in pressure-500#. Final shut-in pressure-150#.

INVOICED

hereby certify that the above well was plugged as herein stated.

DATE 2/5/74  
INV. NO. 8500-W

Signed: K. L. Nichols  
Well Plugging Supervisor