

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
11-1-67
NOV 1 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Et al, Incorporated,

Complete Address 501 Cameron Building, Oklahoma City, Oklahoma. 73106

Lease Name Rice Well No. 1

Location SW-SE-SW Sec. 33 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3797'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Paine Drilling Company, Incorporated,

Address Box "D", Hill City, Kansas. License No. _____

Operation Completed: Hour 9:30AM Day 28 Month 10 Year 1967

The above well was plugged as follows:

226'--7" OD Surface casing, cement circulated with 125 Sx.
Dakota section from 1200' to 1000'.

Circulated hole with heavy mud. Pulled DP to 1220' and displaced 100 Sx. cement thru
DP from 1220' to 750'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
270' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 11/1/67
INV. NO. 6599-W