

KANSAS

*AL*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
7-26-71  
JUL 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address Shields Building, Russell, Kansas.

Lease Name Rice Estate Well No. 1

Location W/2-SW-SW Sec. 33 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 4036'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No.       

Operation Completed: Hour 8:30 AM Day 22 Month 7 Year 1971

The above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru  
DP from 1150' to 825'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 7-29-71  
INV. NO. 4061-2