

KANSAS

M
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
7-8-71
JUL 8 - 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Black Petroleum, Incorporated,

Complete Address 445 O. W Garvey Building, Wichita, Kansas.

Lease Name Law Well No. 1

Location SW-NE-SW Sec. 34 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3975'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kans. License No.

Operation Completed: Hour 3:00 AM Day 5 Month 7 Year 71

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 725'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Shields*
Well Plugging Supervisor

INVOICED

DATE 7-9-71

INV. NO. 2963-W