

KANSAS

12
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1969

CONSERVATION DIVISION
Wichita, Kansas

10-24-1969

15-065-19170-00-00

Operator's Full Name Ivy Oil Company,

Complete Address Box #86, Plainville, Kansas.

Lease Name John Johnson Well No. 1

Location SE-SE Sec. 10 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 10:30 AM Day 18 Month 10 Year 1969

The above well was plugged as follows:

214'--8 5/8" Surface casing, cement circulated.
3917'--4 1/2" casing cemented on bottom with 100 Sx. Top perforations from 3676' to 3680'.
DV Tool set @ 1741' and squeezed with 100 bbl. Chem-Pak.

Sanded well back to 3650' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and
squeezed well initially with 4 sacks hulls and followed with 100 Sx. cement from 700'
to 220' then 20 Sx. cement from 220' to 160' and followed with 3 sacks gel from 160'
to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in press-
ure--250#. Final shut-in pressure--100#. Recovered 2511'--4 1/2" casing. (Mudding and
cementing operations performed by Globe Oilwell Cementing, Incorporated).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 10/27/69
INV. NO. 712-4