

15-065-20210-00-00

Form CP-3
Rev. 6-4-68

KANSAS

22
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
03-20-1970
MAR 20 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. J. Dreiling & Sons, Incorporated.

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Johnson Well No. B-1

Location NE-SW-SW Sec. 10 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3950'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:00 AM Day 15 Month 3 Year 1970

The above well was plugged as follows:

191'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru
DP from 1025' to 700'. Pulled DP to 250' and displaced 25 Sx. cement thru DP from
250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. S. Nichols*
Well Plugging Supervisor

INDEXED
DATE 3/20/70
INV. NO. 1617-U