

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-065-03127-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1966  
12-14-1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Skelly Oil Company,

Complete Address: P.O. Box #649, McCook, Nebraska.

Lease Name Griffith Well No. A-1

Location SW-SW-SW Sec. 11 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth--Plug Back--(3690')

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box # 364, Great Bend, Kansas. License No. 496

Operation Completed: Hour 12:00M Day 10 Month 12 Year 1966

The Above well was plugged as follows:

247'--8 5/8" Surface pipe, cement circulated.  
3960'--5 1/2" Production casing cemented. Well plugged back to 3690'.  
Top perforations from 3681 to 3687.

Sanded well back to 3650', and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well with 30 Sx. gel and 75 Sx. cement.

Cement from 3650' to 3610'. Mud from 3610' to 400'. cement from 400'  
to 200'. Mud from 200' to 30'. Cement from 30' to cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/14/66  
INV. NO. 4462-U

Signed: N. L. Finkel  
Well Plugging Supervisor