

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
10-21-1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-01884-00-00

Operator's Full Name Herman George Kaiser,

Complete Address 4120 E. 51st Street, Tulsa, Oklahoma.

Lease Name Conness Well No. A-2

Location W/2-W/2-SW Sec. 23 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3878'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Charlie Crow Drilling Company,

Address Box #706, Hays, Kansas. License No. 733

Operation Completed: Hour 1:15 PM Day 17 Month 10 Year 1974

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3876'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to  
3846'. Top perforations from 3715' to 3810'. DV Tool @ 1900' with Chem-Pak to surface.  
Pushed plug to 3650', sanded back to 3625 & set 4 Sx. cement with dump bailer. Pulled  
5 1/2" casing (2972') and squeezed well initially with 5 sacks hulls and 12 sacks gel,  
followed with 110 Cu. Ft. cement from 1000' to 675' then 10 sacks gel and 1 sack hulls  
from 675' to 235' and followed with 30 Cu. Ft. cement from 235' to 160' then 3 sacks  
cement from 160' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar.  
Maximum pump-in pressure-750#. FSIP-400#. (Mudding and cementing by Allied Cmtg., Inc.)

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 10/23/74  
WELL NO. 135-W