

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-00601-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1968
CONSERVATION DIVISION
Wichita, Kansas
10-21-1968

Operator's Full Name Herman Geo. Kaiser,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name Conness Well No. A-1

Location SW-SW-SW Sec. 23 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 3870

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 11:00AM Day 12 Month 10 Year 1968

The Above well was plugged as follows:

182'--8 5/8" Surface casing, cement circulated with 150 Sx.

3868'--5 1/2" Production casing cemented on bbtom with 150 Sx. (Temp. Survey @ 3135').

Well plugged back to 3833'. Top perforations @ 3712'.

Pushed plug to 3700', built sand bridge and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well with initially 16 sacks gel with 5 sacks hulls in

initial gel and followed with 100 Sx. cement from 950' to 625' then 11 sacks gel from

625' to 200' and followed with 20 Sx. cement from 200' to 140' then 3 sacks gel from

140' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in

pressure--400#. Final shut-in pressure--200#. (Mudding and cementing operations per-

formed by Allied Cementing Co.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10/21/68

INV. NO. 8658-W