

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20468-00-00

07-15-1971
RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Black Petroleum, Incorporated,

Complete Address 145 O. W. Garvey Building, Wichita, Kansas.

Lease Name McVey Well No. 1

Location SW-NW-NW Sec. 24 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Shields Drilling Company, Incorporated,

Address Shields Building, Russell, Kansas. License No. _____

Operation Completed: Hour 10:00 PM Day 13 Month 7 Year 1971

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru
DP from 1000' to 775'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/15/71
INV. NO. 4000-W