

KANSAS

*2*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-19171-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
10-28-1968

Operator's Full Name Ivy Oil Company,

Complete Address: Box #86, Plainville, Kansas.

Lease Name McCall Well No. B-2

Location SE-SE-NW Sec. 25 Twp. 10 Rge. (E) (W) 23

County Graham Total Depth 4040'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company, Incorporated,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 12:00 M Day 26 Month 10 Year 1968

The Above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3770'--5 1/2" Production casing, cemented on bottom with 75 Sx. Well plugged back to  
3731'. Top perforations @ 3599'.

Pushed plug to 3575' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and  
squeezed well with initially 16 sacks gel with 5 sacks hulls in initial gel and followed  
with 100 Sx. cement from 950' to 625' then 11 sacks gel from 625' to 200' and followed  
with 20 Sx. cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally 10  
Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--600#. Final shut-  
in pressure--300#.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Dickels*  
Well Plugging Supervisor

INVOICED

DATE 10/28/68

INV. NO. 8712-4